

SYSTEM STRENGTHENING/ADDITION IN PABBAR BASIN

Sr.N	DESCRIPTION	Estimated Cost	COD	Source of Funding	IMPLEMENTING AGENCY
1	Construction of 220/400 kV, 2x315 MVA (INITIALLY 1X315 MVA) GIS Sub station at PRAGATINAGAR and LILO of both circuits of 400 kV JHAKRI Abdullapur D/C Line	₹ 167 Crore	2015-16	ADB-Tranche-I	HPPTCL
2	220 KV D/C (Twin MOOSE) Hatkoti-Pragati Nagar Transmission Line	₹ 84 Crore	2015-16	ADB-Tranche-I	HPPTCL
3	220 kV Switching Station at Hatkoti	₹ 45 Crore	2015-16	ADB-Tranche-II	HPPTCL
4	132/220 kV, 2x80/100 MVA Pooling Station at Sunda	₹ 77 Crore	2015-16	ADB-Tranche-II	HPPTCL
5	220 kV D/C (Twin MOOSE) Sunda- Hatkoti Transmission Line	₹ 69 Crore	2015-16	ADB-Tranche-II	HPPTCL
6	66/220 kV sub station at Sunda and 66 kV D/C Line from Andhra to Sunda	₹ 54 Crore	2015-16	Domestic	HPPTCL
7	Additional 315 MVA, 400/220 kV Transformer at ParagatiNagar	₹ 40 Crore	13th Plan	ADB-Tranche-III	HPPTCL

8	132 kV D/C Line from Tangnu Romai HEP to 132/220 kV GIS sub station at Sunda	₹ 26 Crore	2015-16	Domestic	HPPTCL
9	132 kV D/C line from Rupin HEP to 132/220 kV GIS sub station at	₹ 38 Crore	2016-17	Domestic	HPPTCL
TOTAL		₹ 600 Crore			