

LTOA Granted												
Sr.No	Name of Applicant	Month & Year in which LTA Application received	Date from which LTA applied	Date from which LTA granted	Capacity (MW) for which access has been granted	Period of LTA	Point of Interconnection	Point of Drawl	Transmission System used	Distribution system used	Status (LTA Intimation) yes/no	Status (LTA granted) yes/no
1	GMR Bajoli Holi Private Limited	26.03.2015	01.08.2018	01.08.2018	178.20 MW	12 Years	220 kV D/C Bajoli Holi to Lahal Line	Northern region	220 KV D/C (Twin Moose) Line between Bajoli Holi HEP and 220/400 KV Lahal GIS sub-station.	No	Yes	Yes
2	Suryakanta HEP (Nanti)	16.11.2016	01.04.2018	23.06.2018	14 MW	18 years 11 Months	66 KV S/C line on D/C Tower from Nanti to 66 KV yard of Ghanvi-II HEP	Northern region	(i) 33 KV line on D/C structure from Nanti 14 MW HEP to 33/66 KV existing Sub-Station at Nanti including terminal equipment. (ii) 66 S/C line on D/C towers from Nanti to 66 KV yard of Ghanvi-II HEP. (iii) 66 KV D/C line from Ghanvi-II to Ghanvi-I HEP. (iv) 66 KV line from Ghanvi-I HEP to 66/220 KV Sub-Station. (v) 220 KV Bhaba- Kunihar D/C line with one circuit LLO at Kotla Sub-Station.	Yes	Yes	Yes
3	Nanti Hydro Power Pvt. Ltd. (Upper Nanti)	21.11.2016	01.04.2017	01.09.2019	13.5 MW	18 Years 2 Months	66 kv Ghanvi-II HEP	Northern region	(i) 33 KV S/C Line from Upper Nanti 13.50 MW HEP to common interfacing point at Kurmi HEP. (ii) 33 KV D/C Line from common interfacing point at Kurmi HEP to 33/66 KV existing Substation at Nanti including terminal equipment. (iii) 66 KV S/C Line on D/C towers from Nanti to 66 KV yard of Ghanvi-II HEP. (iv) 66 KV Line from Ghanvi-II to Ghanvi-I HEP. (v) 66 KV D/C line from Ghanvi-I HEP to 66/220 KV Substation at Kotla. (VI) 220 KV Bhaba- Kunihar D/C line with one circuit LLO at Kotla Substation.	Yes	Yes	Yes
4	M/s Taranda Hydro Power Pvt. Ltd. (Rala)	21.11.2016	01.09.2017	30.06.2019	13 MW	20 Years	66/220/400 KV Sub-Station of HPPTCL at Wangtoo i/c terminal equipment.	Northern region	(i) 66 KV S/C Line From Rala HEP to 66/220/400 KV Sub-Station of HPPTCL at Wangtoo i/c terminal equipment. (ii) 66/220/400 KV (66/220, 2x80/100 MVA + 2x315 MVA, 220/400 KV) Sub-Station at Wangtoo by LLO of both circuits of 220KV Kashang-Bhaba D/C Line and 400 KV Wangtoo-Abdullapur D/C Line.	No	Yes	Yes
5	HP Power Corporation Ltd (Swara Kuddu)	07.07.2018	15.08.2019	30.10.2020	111 MW	25 Years	220 kV D/C Snail to Hatkoti line	Northern Region	(i) 220 KV D/C Line From Snail to Hatkoti. (ii) 220 KV Switching Station Hatkoti. (iii) 220 KV D/C Line from Hatkoti S/s to 220/400 KV Substation at Pragati Nagar,Gumma. (iv) 220/400 KV, 2x315 MVA Substation at Pragati Nagar with LLO of both circuits of 400 KV Jakhri-Abdullapur D/C Line.	No	Yes	Yes
6	HP Power Corporation Ltd (Kashang stage-I)	18.01.2019	31.03.2019	02.11.2019	65 MW	25 Years	220 KV D/C Line from Kashang HEP to Wangtoo	Northern Region	(i) 220 KV D/C Line from Kashang HEP to Wangtoo i/c terminal equipment. (ii) 66/220/400 KV (66/220 KV, 2X80/100 MVA + 220/400 KV, 2X315 MVA) Sub-Station by HPPTCL at Wangtoo by LLO of both circuits of 220 KV Kashang-Bhaba D/C line and 400 KV Karcham Wangtoo-Abdullapur D/C Line.	No	Yes	Yes

LTOA Application In Process

Sr.No	Name of Applicant	Month & Year in which LTA Application received	Date from which LTA applied	Date from which LTA granted	Capacity (MW) for which access has been granted	Period of LTA	Point of Interconnection	Point of Drawl	Transmission System used	Distribution system used	Status (LTA Intimation) yes/no	Status (LTA granted) yes/no
1	Kanchanjunga Company Pvt. Ltd (Baragaon).	22.10.2011	30.09.2013	In Process	24 MW	25 Years	220/33 kV Phojal Substation	Northern Region	220/33 kV Phojal Substation by LILO of 220 kV AD Hydro Prini to Nalagarh line	No	Yes	No
2	Jagdambey Hydro Projects (Kuwarsi-II)	01.11.2016	Sep-17	Intimated not signed	51 MW	25 Years	220/66 kV Heiling Substation	Northern Region	66 KV D/C line from Salun Power Station to 66/220 KV Sub-Station at Heiling and 66/220 KV, 100 MVA GIS Sub-Station at Heiling with LILO of one circuit of 220 KV Bajoli Holi-Lahal D/C Line at Heiling.	No	Yes	No
3	Cosmos Hydro Power Pvt Ltd (Chanju-II)	25.05.2018	01.06.2021	Intimated not signed	19.8 MW	25 Years	S/C LILO of 132 kV D/C Kurthla Bathri line	Northern Region	132/220 KV, 2X100 MVA substation of HPPTCL under construction Mazra by LILO of both circuits of 132 KV Kurthala-Bathri D/C Line.	Yes	Yes	NO
4	Ugreshi Hydro Power Private Limited (Umpli HEP)	10.08.2018	Mar-20	Intimated from 31.08.2021 but yet to be signed	10	25 Years	66 kV Substation Nirmand	Northern Region	66 kV Substation Nirmand , 66 kV D/C Nirmand Substation to Kotla (HPSEBL) Line	Yes	Yes	No
5	Panchhor Hydro Power Private Limited (Wanger Homte 24.60 MW)	03.10.2018	30.09.2019	PPA signed by IPP with HPSEBL hence LTA not required, IPP is being pursued for cloing of LTA application	24.60 MW	25 Years	66/220/400 kV Wangtoo Substation	Northern region	66/220/400/ KV (66/220 KV, 2x80/100 MVA + 2X315 MVA, 220/400 KV) Substation of HPPTCL at Wangtoo by LILO of both circuits of 220 KV Kashang-Bhaba D/C line and 400 KV Wangtoo -Abdullapur D/C line.	No	Yes	PPA with HPSEBL
6	Bhang Hydel Power Project	23.05.2019	March, 2020	Intimated not signed	9 MW	25 Years	33 kV Palchan Substation	Northern Region	(i) 33 KV GIS switching station at Palchan. (ii) 33 KV Palchan- Prini D/C line 33/220 KV, 31.5 MVA Substation in the yard of Allain Duhangan HEP. In the absence of 33 KV GIS switching station at Palchan, access shall be granted at 33 KV Palchan Prini D/C line.	No	Yes	No
7	Bharmani Hydro Power Ltd (Dera)	07.06.2019	April,2023	IPP in process of signing PPA with HPSEBL and is being pursued for closing of LTA Applicatrion	5 MW	25 Years	33 kV Lahal Holi-II Switchyard	Northern Region	33/220 kV Lahal through HPSEBL System	Yes	No	No
8	Kangra Hydro Project (Gaj-III)	13.08.2019	April,2020	PPA signed by IPP with HPSEBL hence LTA not required, IPP is being pursued for cloing of LTA application	5 MW	25 Years	132/33 kV Chambi	Northern Region	132/33 kV Substation Chambi	Yes	Yes	PPA with HPSEBL
9	Tidong Power Generation Ltd	Oct-19	1.10.2021	In Process	100 MW	25 years	S/C LILO of 220 kV D/C Kashang Wangtoo Line	Northern region	220 KV Kashang Wangtoo- Bhaba D/C Line, and 400/220/66 KV Substation at Wangtoo by LILO of 400 KV Karcham Wangtoo Abdullapur D/C line of PGCIL and LILO of 220 KV Kashang - Bhaba D/C line at Wangtoo.	No	Yes	No
10	HP Power Corporation Ltd (Kashang Stage II & III)	Oct-19	October, 2025	In Process	(2x65)MW	25 years	220 kV D/C Kashang to Bhaba line	Northern Region	220 KV Kashang Wangtoo- Bhaba D/C Line, and 400/220/66 KV Substation at Wangtoo by LILO of 400 KV Karcham Wangtoo Abdullapur D/C line of PGCIL and LILO of 220 KV Kashang - Bhaba D/C line at Wangtoo.	No	No	No
11	JSW Energy (Kutehr)	25.02.2021	Not indicated	In Process	240 MW	25 years	S/C LILO of 400 kV D/C Lahal Chamera Line	Northern Region	By S/C LILO of 400 kV D/C Lahal Chamera Lin	No	No	No


Assistant Engineer
Planning, HPPTCL Shimla-05